

Pontilly Neighborhood Stormwater Network

City of New Orleans

February 14, 2019



Resilience + Sustainability

CITY OF NEW ORLEANS

Agenda

Welcome

Valerie Bouldin, Mayor's Office of Neighborhood Engagement

Project Overview

Meagan Williams, Department of Public Works

, CDM Smith

Jessica Addison, *CDM Smith*Jessica Watts

What to Expect During Construction

Natalie Manning, Office of Resilience & Sustainability/RoadworkNOLA

Discussion

Valerie Bouldin, Office of Neighborhood Engagement







Ground Rules

- Presentation will precede public comment
- Please limit questions to the project area
- Please fill out a comment card to provide a comment/ask a question
- Please raise your hand and your comment card will be collected by a staff member
- There is a two-minute time limit on questions
- A staff member will hold the microphone for you
- You may not yield time to another speaker








Project Overview







Pontilly Neighborhood Stormwater Network Project Map









Why Pontilly?...

- Flooding occurs during yearly heavy rainstorm events
- Current drainage system and stormwater pipes can only accommodate for a 2-year flood event
- Excavating and replacing the current piping system is expensive and intrusive
- Post Katrina, many lots are still vacant
- Soil subsidence through over pumping and flooding compromises the streets and home foundations







History

April 2008
Pontilly Neighborhood approached NORA

with design concepts

to mitigate flooding

2009

NORA applied for a FEMA Grant for Pontilly Stormwater Mitigation Project

2010

NORA was awarded the \$15 Million Grant; NORA issued RFP; Selection committee selected the winning design team: CDM Smith

2012

State/City/NORA
executed an
agreement to
begin the design
phase of the
Pontilly
Stormwater
Mitigation Project

2009

"Pontchartrain
Park + Gentilly
Woods Landscape
Manual"
Longue Vue
House & Gardens
partnered with
University Design
Studios

2010-2011

"Dwyer Canal
Revitalization"
booklet produced
by
Pontilly
Neighborhood
partnered with
Long Vue House
and Gardens







Team

Owner

- New Orleans Redevelopment Authority (NORA)
- City of New Orleans, Department of Public Works

Design Team

- CDM Smith
- Dana Brown & Associates
- Hatch

Construction Contractor

Fleming Construction








Funding

FEMA HMGP grant

- Total \$15 Million
- Divided into 2 phases:
 - Phase 1 Design and engineering (\$1.5M)
 - Phase 2 Construction of design (\$13.5M)
- Limitations
 - Funding covers majority of construction cost
 - Activities related to stormwater infrastructure
 - Does not cover enhancements such as:
 - Pedestrian bridge
 - Benches










Existing Conditions / Problems
















Pontchartrain Park Flooding, July 2012










Proposed Solutions








Greater New Orleans Urban Water Plan





Retain: Hold the drop of rain as close to where it falls as possible

Detain: Store runoff temporarily in planned locations


Drain: Increase the ability of infrastructure to flow







Duration









Proposed Solution | Existing Condition 1-Year Storm









Proposed Solution | Improved Condition 1-Year Storm










Proposed Solution | Improvements 1-Year Storm










Proposed Solution | Improvements 2-Year Storm









Green Infrastructure Project Features







Pervious Pavement











5,875 LF of Pervious Pavement w/ Total Storage

= 37,760 cf

 $= 282,465 \, gal$

= 3,530 bathtubs









Stormwater Lots & Parks








36 Stormwater Lots w/ Total Storage

- = 412,900 cf
- = 3,088,700 gal
- = 38,610 bathtubs

























Total Storage

= 444,500 cf = 3,325,090 gal

= 41,560 bathtubs









Street Basins







24 Street Basins w/ Total Storage

- = 68,420 cf
- = 511,820 gal
- = 6,400 bathtubs













Permeable pavers

Street Basin

Urban Bioswale










Urban Bioswales











Total Storage

= 65,190 cf = 487,655 gal

= 6,095 bathtubs











Total Storage

- = 126,400 cf = 945,540 gal
- = 11,820 bathtubs









Dwyer Canal











Additional Storage

- = 35,000 cf = 261,800 gal
- = 3,270 bathtubs









What to Expect During Construction

Temporary construction impacts

- Additional construction equipment
- Limited parking availability
- Sounds
- Dust



- Construction signage placed around the sites.
- Any temporary closures will be communicated in advance.
- Any changes to garbage and US Postal services will be communicated in advance.
- Residents will be informed throughout construction.

Regular work hours are Monday-Friday 7:00 a.m. to 5:30 p.m. Permission for occasional weekend work may be granted, if required.







Road

Construction

Ahead

Phases & Details


- Streets will be closed two blocks at a time and returned to service before moving to the next two blocks
- On streets that will not be fully reconstructed, only one lane will be closed at a time
- In the event of full block closures, 48 hours notice will be given to residents







Proposed Staging Area










Schedule

- March 2019 to September 2020
- In general, crews will perform work Monday through Thursday 7:00am to 5:30pm, and Fridays as needed.
 Schedule may be subject to change depending on weather.










Keeping You Informed

Roadwork.nola.gov









Stay Connected

ROADWORK.NOLA.GOV



Resilience + **Sustainability**

CITY OF NEW ORLEANS



Facebook.com/roadworkNOLA



@roadworkNOLA



@roadworkNOLA



We have joined NextDoor!



504.658.ROAD (7623)



roadwork@NOLA.gov



Monthly Newsletter Updates











@resilientNOLA



@resilientNOLA

Contact Information

Natalie Manning, Outreach Specialist 504-658-ROAD (7623) roadwork@nola.gov







Questions / Discussion





